REFURBISHMENT PROJECT



Rhyl Leisure Centre

Client	Rhyl Leisure Centre
Site Address	Grange Road, Rhyl, Denbighshire, North Wales.
Facility	102.0m x 72.0m
Pitch System	 New VHAF® NottsSward 1300 needlepunched sand filled grass LAID ONTO EXISTING - Sand Envelope System® Performance Control Layer Dynamic granular stone base Underlying piped drainage system
Other Features	 Permanent and Semi -Permanent painted lines for football, hockey & 5-a-side Football New self-weighted, free standing football and hockey goals 2no. New macadam surfaced goal recesses (10m x 3m) New 4.50m rigid panel system perimeter fencing New 1.20m internal spectator fencing, creating an additional 8m x 102m warm up/sprint area
Dates	Resurfaced – June 2009 Originally Built - 1992
Specialist Builder	Dura Sport Ltd
Refurbishment Cost	£242,000 + VAT
Point of Interest	The original construction was installed in 1992. The project in 2009 was to replace the old VHAF® NottsSward sand filled surface with a replacement high quality multi purpose synthetic grass & replace the existing dangerous perimeter fencing, provide new recesses and create an internal training/sprint/warm up area by installing a 1.20m high spectator fence inside the overall pitch footprint.
	The existing Sand Envelope System® & dynamic base construction has proven to last the life of 2 carpets at sites throughout the UK providing customers with a system that can be reused rather than replaced and reduce the costs of refurbishment in comparison to other performance layers and shock-pads.
Sports	✓ Football ✓ Hockey ✓ Tennis ✓ Netball ✓ Aerobic Activities and games

